

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-21168-00-00

OCT 19 2001

LEASE NAME Srajer

Rec'd
1023-01
RECEIVED
OCT 23

TYPE OR PRINT

WELL NUMBER 1-29

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from (S) Section Line

2970 Ft. from (E) Section Line

SEC. 29 TWP. 22 RGE. 33 (W) or (N)

KCC WICHITA

COUNTY Finney

LEASE OPERATOR Berexco Inc.

Date Well Completed 4/9/93

ADDRESS PO Box 20380

Plugging Commenced 9-19-01

PHONE (316) 265 3311 OPERATORS LICENSE NO. 5363

Plugging Completed 9-20-01

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-18-01 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPI Depth to Top 4734 Bottom 4744 T.D. 4980'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1746	—
				4 1/2	4979	1822

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each so
CIBP + 2 5x 4700 CIBP + 2 5x 3000 Recover & pull 4 1/2 to 1770. Circ.
hole w/mud 40 5x 1770 to 1650 30 5x 900 to 800 10 5x 40 to 0
Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BEREXCO INC.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

EVAN C. MAYHEW (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) Evan C Mayhew

(Address) P O Box 20380, Wichita, KS 67208

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 2001

Betty J. Terbush
Notary Public

My Commission Expires: 4-11-04

