

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Finney County, Sec. 29 Twp. 22s Rge. 33w (E) (W)

Location as "NE/CNW/SW" or footage from lines se se ne

Lease Owner Amerillo Natural Gas Co.

Lease Name Collins Well No. 1

Office Address Box 1257 Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed 2-26 1965

Application for plugging filed 4-1 1966

Application for plugging approved 4-4 1966


Plugging commenced 4-6 1966

Plugging completed 4-11 1966

Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production 3-25 1966

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edd Eaves

Producing formation Paris 4448-4476 Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4476 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	396	0
				4 1/2	4476	2520

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mix 15 sacks cement to plug off perforations at 4448'. Stop plug at 4300 feet. Shoot pipe loose at 2520 and lay down to 450'. Pump 35 sacks cement at 450 to 350 feet. Finish laying down casing and put 15 sacks cement at 45 feet to 0'. Cut 8 5/8 off 3 feet below ground level and cap same.

RECEIVED  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1966

CONSERVATION DIVISION  
Wichita Kansas

CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service

Address Box 506 Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.

I T. W. Mahoney (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I T. W. Mahoney  
Box 1257 Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of April, 1966

George W. Carnahan  
Notary Public.

My commission expires January 24, 1968

Amarillo Natural Gas Co. Inc.  
Collins # 1  
Finney County Kansas  
SEC 29-TWP 22 RANGE 33

8 5/8" Set 387' 400 Sx.  
Cement Circulated  
4 1/2" Set 4809' 200 SX.  
Cement Circulated

Surface soil & Sand	0-100
Sand & Clay	100-400
Shale	400- 940
RED Bed	940-1125
RED BED & Shale	1125-1675
Shale & Sand	1675-1850
Anhydrite	1850-1906
Sand & Shale	1906-2120
Shale & Shell	2120-2309
Shale & Lime	2309-2530
Lime & Shale	2530-2677
Lime	2677-2845
Lime & Shale	2845-2980
Lime	2980-3198
Lime & Shale	3198-3330
Shale & Chalk	3330-3557
Lime & Shale	3557-3659
Lime & Chalk	3659-3845
Lime	3845-4514
Sand & Lime	4514-4570
Lime	4570-4810
TD	4810

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1966  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
APR 26 1966  
CONSERVATION DIVISION  
Wichita, Kansas

This is a true and exact copy of the formation, taken from  
The Daily Drilling Reports.

MAHONEY DRILLING COMPANY INC.

J. W. Mahoney

STATE OF KANSAS  
COUNTY OF SEWARD

Sworn to before me this 8 Day of February, 1965.

George W. Carnahan, Jr.  
Notary Public

MY Commission Expires January 24, 1968.

