

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-055-20411-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Finney County, Sec. 33 Twp. 22S Rge. 33W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NE


Lease Owner W. L. Hartman Estate
Lease Name Damme Well No. 25
Office Address Box 54, Wichita, Ks. 67201
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed July 6, 1980
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 6, 1980
Plugging completed July 6, 1980
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. Owen of Pratt, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4900'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	412.67'	8-5/8"	412.67'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plugged Hole w/50 sax cement @ 2750',
40 sax cement @ 390', 10 sax cement
@40', 5 sax cement in rat hole.
Job Completed @ 2 P.M.

7-16-80

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of JUL 16 1980 sheet)

Name of Plugging Contractor Allied Cementing

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John R. Bartholomew of Sage Drilling Co. (owner or operator)
of the above described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
222 Sutton Place, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 80

Louise L. Whittier
Notary Public.

My commission expires _____



DRILLERS LOGDAMME NO. 25

CASING RECORD: OPERATOR: W. L. Hartman Estate DESCRIPTION:
 8-5/8" set @ 412.67 CONTRACTOR: Sage Drilling Co., Inc. SE NE
 w/300 sax cement COMMENCED: June 25, 1980 Sec. 33-22S-33W
 Finney County,
 Kansas.
 TOTAL DEPTH: COMPLETED: July 6, 1980
 4900'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	420	
Sand	420	505	
Sand & Red Bed	505	1307	
Shale & Sand	1307	1846	
Shale	1846	2375	
Shale & Lime	2375	2520	
Lime & Shale	2520	3063	
Shale & Lime	3063	3263	
Lime & Shale	3263	4465	Ran DST #1
Lime & Shale	4465	4510	Ran DST #2
Lime & Shale	4510	4820	Ran DST #3
Lime & Shale	4820	4900	Logged Hole Ran DST #4 D. & A.

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.


By John R. Bartholomew
 John R. Bartholomew

Subscribed and sworn to before me on the 8th day July, 1980.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 16 1980

Louise K. Whitted
 Louise K. Whitted, Notary Public



CONSERVATION DIVISION
 Wichita, Kansas