


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Finney County, Sec. 34 Twp. 22S. Rge. (E) 33 (W)  
Location as "NE/CNW&SW" or footage from lines C NW SE  
Lease Owner W. L. Hartman  
Lease Name Finnup "D" Well No. 2  
Office Address P. O. Box 54, Wichita, Kansas 67201  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 5, 19 73  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 5, 19 73  
Plugging completed November 5, 19 73  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	451'	8-5/8"	451'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 2700 Feet,  
90 sax Cement Plug; Mud to 450 Feet, 40  
sax Cement Plug; Mud to 40 Feet, 1/2 sax  
Hulls, Plug Bridged & 10 sax Cement to  
Base of Cellar; 2 sax Cement in Rat Hole.  
Job Completed @ 10:45 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Dowell  
Address Liberal, Kansas

(If additional description is necessary, use BACK of this sheet)

STATE OF KANSAS COUNTY OF SEDGWICK  
Clarence Michael of Sage Drilling Co. (employee or owner or owner or operator of the above described well)


Being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael  
500 Bitting Bldg., Wichita, Ks. 67202  
(Address)

Subscribed and Sworn to before me this 8th day of November, 19 73.

Louise K. Whitted  
Louise K. Whitted - Notary Public.

My commission expires November 26, 1974.



DRILLERS LOGFINNUP "D" NO. 2

CASING RECORD:	OPERATOR: W. L. Hartman	DESCRIPTION:
8-5/8" @ 451' w/300 sax cement	CONTRACTOR: Sage Drilling Co.	C NW SE Sec. 34-22S-33W Finney Co., Kansas
TOTAL DEPTH: 4900'	COMMENCED: October 24, 1973	ELEVATION: 2877KB
	COMPLETED: November 5, 1973	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	455	
Shale	455	1540	
Shale & Sand	1540	2376	
Lime & Shale	2376	2750	
Lime	2750	2900	
Shale	2900	3070	
Shale & Lime	3070	3400	
Lime & Shale	3400	3878	
Lime	3878	4900	

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael  
Clarence Michael



Subscribed and sworn to before me this 8th day of November, 1973.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.