

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-055-21,049-0000

LEASE NAME GCCC

WELL NUMBER 1-10

810 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 10 TWP. 22S RGE. 34 (S or W)

COUNTY Finney

Date Well Completed 1-27-92

Plugging Commenced 1-27-92

Plugging Completed 1-27-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500

PHONE#(316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-27-92 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4975'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	1772'	8-5/8"	1772'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plug with Halliburton pump truck using 60-40 Pozmix, 6%gel. Set 1st plug @ 3200' w/100 sks. 2nd plug @ 1780' w/50 sks. 3rd plug @ 900' w/40 sks. 4th plug @ 40' w/10 sks. 10 sacks in mousehole and 15 sacks in rathole. Plugging complete 6:30 P.M. 1-27-92.

(If additional description is necessary, use BACK of this form.)

2-7-92

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 110 S. Main, Suite 500, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK

McCoy Petroleum Corporation (Employee of Operator, Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 5 day of February, 19 92



Deborah Ann Paulus
Notary Public

Commission Expires: 1-8-96