

STATE CORPORATION COMMISSION
Wichita State Office Building
130 S. Market, Room 2078
Wichita, Ks 67202

K.A.R.-82-3-117

API NUMBER 15- 055-21610 -0000

LEASE NAME Barrett

WELL NUMBER 20-5

990 FSL Ft. from S Section Line

990 FEL Ft. from E Section Line

SEC. 20 TWP 22S RGE 34W (E) OR (W)

COUNTY Finney

Date Well Completed 2/18/98

Plugging Commenced 10/30/98

Plugging Completed 10/30/98

**TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.**

LEASE OPERATOR Sonat Exploration Company

ADDRESS 14000 Quail Springs Parkway, Suite 100, Oklahoma City, Ok 73134

PHONE # (405) 749-7108 OPERATORS LICENSE NO. 31594

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/28/98 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Y If not, Is well log attached? N

Producing Formation Dry Depth to Top _____ Bottom _____ T. D. 4850

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1819	0
				5 1/2	4680	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Set CIBP @ 4450, set CIBP @ 4350, set CIBP @ 3950 and dumped 2 sks cement on plug @ 3950 to 3930, load 5 1/2 csg from surface w/ 92 bbl mud, perforate the 5 1/2 csg @ 1869 circulate cmt from 1869 to 4, w/365 sks 40/60 poz + 6% gel by Halliburton pump truck.

Name of Plugging Contractor Sonat Exploration Company License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sonat Exploration Company

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

J. C. Morris (Employee of Operator) or (Operator)

of the above-described well, being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that 11-9-98 the same are true and correct, so help me God.

(Signature) x J. C. Morris

(Address) 14000 Quail Springs Parkway, Suite 100, Oklahoma City, Ok 73134

SUBSCRIBED AND SWORN TO before me this _____ day of _____ 19____

Notary Public

My Commission Expires: _____