

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20,997-0600

LEASE NAME Six-M Farms "E"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-22

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 22 TWP. 22 SRGE. 34 or (W)

COUNTY Finney

Date Well Completed 5-21-91

Plugging Commenced 5-21-91

Plugging Completed 5-21-91

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-21-91 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

5-29-91

RECEIVED

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	1960'	8-5/8"	1960'	None

MAY 29 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plug and abandon using 60-40 Pozmix, 6% gel and 1/2# flocele. Set 1st plug @ 2800' w/100 sks cement. 2nd plug set @ 1975' w/50 sks cement. 3rd plug set @ 1100' w/50 sks cement. 4th plug set @ 500' w/30 sks cement. 5th plug set @ 40' w/10 sks cement. 15 sacks in ratehole and 10 sacks in mousehole. Plugging complete @ 7:30 P.M. 5-21-91

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BEREDCO, Inc. License No. 5147

Address Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500
Wichita, KS 67202



DEBORAH ANN PAULUS AND SWORN TO before me this 24 day of May, 19 91

Deborah Ann Paulus
Notary Public

My Commission Expires: 1-8-92