

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

21049

API NUMBER 15-055-21,49-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500 PHONE # (316) 265-9697

LEASE (FARM) GCCC WELL NO. 1-10 WELL LOCATION 150' N of C SW SW COUNTY Finney

SEC. 10 TWP. 22S RGE. 34 (E) or (W) TOTAL DEPTH 4975' PLUG BACK TO

Check One:

OIL WELL  GAS WELL  D & A X SWD or INJ WELL  DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 1772' CEMENTED WITH 675 SACKS

CASING SIZE  SET AT  CEMENTED WITH  SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug with 60-40 Pozmix, 6% gel. Set 1st plug @ 3200' w/100  
sks cement. 2nd plug @ 1780' w/50 sks cement. 3rd plug @ 900' w/40 sks cement. 4th plug  
@ 40' w/10 sks cement. 10 sacks in mousehole and 15 sacks in rathole..

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-27-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE  
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, Kansas

PLUGGING CONTRACTOR Sweetman Drilling, Inc. LICENSE NO. 5658

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202 PHONE # (316) 265-5561

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Daryl Hanson*  
(Operator or Agent)

DATE: 2-5-92

*Rec'd 2-7-92*  
RECEIVED  
STATE CORPORATION COMMISSION  
FEB 07 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS