

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-055-20,997-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500. PHONE # (316) 265-9697

LEASE (FARM) Six-M Farms "E" WELL NO. 1-22 WELL LOCATION SW SW NW COUNTY Finney

SEC. 22 TWP. 22S RGE. 34  or  TOTAL DEPTH 5000' PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A  SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 1960' CEMENTED WITH 835 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Plug using 60-40 Pozmix 6% gel and 1/4# Flocele. Set

1st plug @ 2800' w/100 sks. Set 2nd plug @ 1975' w/50 sks. Set 3rd plug @ 1100' w/50 sks.

Set 4th plug @ 500' w/30 sks. Set 5th plug @ 40' w/10 sks. 15 sks in rathole and 10 sks

in mousehole. (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? Yes  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5-21-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson **RECEIVED**  
STATE CORPORATION COMMISSION PHONE # (316) 532-5292

ADDRESS Kingman, Kansas MAY 20 1991 5-29-91

PLUGGING CONTRACTOR BEREDCO, Inc. **CONSERVATION DIVISION** LICENSE NO. 5147  
Wichita, Kansas

ADDRESS Wichita, KS 67202 PHONE # (316) 265-2856

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Daryl Hanson*  
(Operator or Agent)

DATE: 5-24-91