

6-3-88 15-057-20046-0001 ¹⁴⁸
R

To: 1 061106
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-057-20,046-A
C NW SE, SEC. 11, T 25 S, R 22 W 4E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9421
Operator: Boger Brothers Drilling Inc.
Name & Address P.O. Box 723
Great Bend, KS 67530

Lease Name Demuth Well # 1
County Ford 37.38
Well Total Depth 1150 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling Inc. License Number 9421
Address P.O. Box 723, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 3 Month: 6 Year: 19 88

Plugging proposal received from Ruth

(company name) Boger Brothers Drilling Inc. (phone) 316-792-8151

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 720' with 50 sx cement, 2nd plug at 390' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 p.m. Day: 3 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 720' with 50 sx cement,

2nd plug at 390' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 6 1988 6-6-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Drilled out of old hole at 720'.
(If additional description is necessary, use BACK of this form.)

INVOLVED (11/10/88) observe this plugging.

DATE 7-13-88

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 21302

NOTICE OF INTENTION TO DRILL

15-057-20046-0001

04WVO

(see rules on reverse side)

Expected Spud Date... May 31, 1988

API Number 15-057-20,046-A

OPERATOR: License # 9421
Name: Boger Brothers Drilling, Inc.
Address: P. O. Box 723
City/State/Zip: Great Bend, KS 67530
Contact Person: Dale Smith
Phone: 316-792-8151

C. NW. SE. Sec. 11... Twp. 25. S, Rg 22... XX West
1980... Ft. from South Line of Section
1980... Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # Company Toole

Nearest lease or unit boundary line ... feet
County... Ford...
Lease Name... Demuth... Well #... 1...
Ground surface elevation... 2386... feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water...
Depth to bottom of usable water...
Surface pipe by Alternate: X 2
Surface pipe planned to be set... 364...
Conductor pipe required... None
Projected Total Depth... 4850... feet
Formation... Cherokee

Well Drilled For: Oil Storage X Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
X OWVO Expl Wildcat Cable

If OWVO: old well info as follows:
Operator... Mull Drilling Co...
Well Name... #1 Demuth...
Comp Date... 5-29-73... Old Total Depth... 4795...

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date... 5-24-88... Signature of Operator or Agent... Title... Geologist

For KCC Use:
Conductor Pipe Required... feet; Minimum Surface Pipe Required... 364... feet per Alt.
This Authorization Expires... 1-25-88... Approved By... 5-25-88

EFFECTIVE DATE: 5-30-88

moving in on 5-28-88
will start washing down 5-31
OR 88

C. NW. SE. Sec. 11... Twp. 25... S, Rg. 22... X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. Base Anhydrite or formation with... 50... SX... feet of...
2nd plug @ ft. deep. 650' or formation with... 50... feet of...
3rd plug @ ft. deep. 390... or formation with... 40... feet of...
4th plug @ ft. deep. 0-40... or formation with... 10... feet of...
5th plug @ ft. deep... or formation with... feet of...
(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

720
PUSHER Ruth
TD 1150 FORMATION
SURFACE PIPE 8 5/8 @ 364
ANHYDRITE ELEVATION 6-3-88
STARTING TIME & DATE 11:00 AM
COMPLETION TIME & DATE 12:45 PM
1st PLUG @ 720' FT. W/ 50 SX
2nd PLUG @ 390 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 20 SX
Helix Cement Co. 6/4/88 6:30 PM
TECHNICIAN S.D.
Remarks: Drill out of hole @ 20 - JUN - 6 1988 CONSERVATION DIVISION Wichita, Kansas

RECEIVED STATE CORPORATION COMMISSION JUN - 6 1988 CONSERVATION DIVISION Wichita, Kansas