

5-30

6 061871

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-15021-0000  
SW \_\_\_\_\_, SEC. 21, T 16 S, R 11 W/EX

1650 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5271

Lease Name Seyfert B Well # 12

Operator Name: Sara Kahan Trustd/b/a SK OTI  
Address: Box 559

County Barton 107.90

Tulsa, Ok. 74101

Well Total Depth 3320 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 225

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 11:00 AM Day: 30 Month: May Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 poz 8% gel 2 sks Hulls.

RECEIVED  
STATE CORPORATION COMMISSION

MAY - 6 1989

07-06-89

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Gilbert C. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 PM Day: 30 Month: May Year: 19 89

ACTUAL PLUGGING REPORT 10 3/4" set at 225' w/200' sks. 5 1/2" set at 3314' w/200 sks.

Open hole 3314'. Plugged bottom w/sand and 5 sks cement to 3250'. Shot pipe three times and recovered 2000'. Pumped in 5 1/2" casing and circulated cement from 800' to surface between 5 1/2" and 10 3/4". Pulled all casing and filled to surface w/230 sks cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(I did observe this plugging.)

DATE 7-5-89

Signed Gilbert C. Scheck  
Gilbert C. Scheck  
Marvin Miller

INV. NO. 25231