

4-020090

15-009-15012-0000

198
R

3-28

API number: 15- - (01/23/46)

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

N SE SE /4 SEC. 21 , 16 S, 11 W
900 feet from S section line
900 feet from E section line

Operator license# 30151

Lease: Seyfert Well # 3

Operator: Eason Services
Address: 2 West Second Street
Tulsa, Oklahoma 74103

County: Barton 109.49
Well total depth 3369 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 195 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Testing & Salvage License# 03952

Address: P.O. Box 347, Chase Kansas 67524

Company to plug at: Hour: _____ Day: 28 Month: March Year: 1996

Plugging proposal received from: Ron Kelso

Company: Mike's Testing & Salvage Phone: 316 278 2346

Were: 8 5/8" Surface casing set @ 195' w/125 sacks; 5 1/2" Production casing set @ 3360' w/150 sacks; Open hole from 3360' to 3369'; Bridge Plug set @ 2700'; Elevation @ 1924'; Total depth - 3369'; Plug back total depth - 2269'; Dakota 224-474'; Anhydrite 752-790' Salt Section 1192-1432';

Ordered 125 sx 60/40 pozmix 10% gel w/ 1/4# flowcel /sx, w/ 500# hulls

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00 PM, Day: 28, Month: March, Year: 1996

Actual plugging report: Bridge plug set @ 2700'; Production casing perforated @ 1475'; Tubing was pulled to 1499'; Pumped 100 sx cement w/500# hulls down tubing; Pulled tubing out of hole; Tied onto backside and tested for previous cement - backside pressured to 300# immediately; Tied onto production casing and pumped 25 sacks; Maximum pressure - 100#s; Ending pressure - 100#s; Completion time: 1:00 PM

Remarks: Allied Cementing performed the cement job.
Condition of casing(in hole): GOOD _____ BAD X Anhy.plug: YES X
Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X
Plugged through TUBING X, CASING _____ Elevation: 1924 GL

I did not observe the plugging.

RECEIVED
KANSAS COM
1996 APR - 1 A 10:09
4-1-96
(agent)

INVOICED
DATE 4-10-96
INV. NO. 45176