

4-020091 15-009-19252-0000

197
R

3-29

API number: 15- - (02/07/46)

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SW SE /4 SEC. 21, 16 S, 11 W
330 feet from S section line
1650 feet from E section line

Operator license# 30151

Lease: Seyfert Well # 4

Operator: Eason Services

County: Barton

109.49

Address: 2 West Second Street

Well total depth 3369 feet

Tulsa, Oklahoma 74103

Conductor Pipe: 0 inch @ 0 feet

Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well ☒, Gas well ☐, Input well ☐, SWD ☐, D & A ☐

Plugging contractor: Mike's Testing & Salvage

License# 03952

Address: P.O. Box 347, Chase Kansas 67524

Company to plug at: Hour: Day: 29 Month: March Year: 1996

Plugging proposal received from: Ron Kelso

Company: Mike's Testing & Salvage

Phone: 316 278 2346

Were: 8 5/8" Surface casing set @ 213' w/125 sacks; 5 1/2" Production casing set @ 3363' w/150 sacks; Open hole from 3363' to 3368'; Cast Iron Bridge Plug set @ 3190'; Production perforations @ 3072-3188'; Elevation @ 1898'; Total depth - 3369'; Plug back total depth - 3290'; Anhydrite 724-1172';

Ordered 190 sx 60/40 pozmix 10% gel w/ 1/4# flowcel/sx, w/500# hulls

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All ☒, Part ☐, None ☐

Completed: Hour: 1:00 PM, Day: 29, Month: March, Year: 1996

Actual plugging report: Bridge plug set @ 2706'; Production casing perforated @ 1475', 750', 250'; Tubing was pulled to 1508'; Pumped 160 sx cement w/450# hulls down tubing; Cement did not circulate: Tied onto backside and tested for previous cement - backside pressured to 200# immediately and held at 100# until cement vented out of slips on wellhead; Pulled tubing to 270'; Pumped 20 sx w/50# hulls to circulate to surface; Slobbered in 10 additional sacks cement to fill production casing to surface; Cement level remained stationary in production casing @ surface; Completion time: 1:00 PM.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD BAD ☒Anhy. plug: YES ☒ NO ☐Bottom plug(in place): YES, CALC ☒, NO ☐Dakota plug: YES ☒ NO ☐Plugged through TUBING ☒, CASING ☐

Elevation: 1898

I did ☒ did not ☐ observe the plugging.

(agent)

Form CP-2/3

DATE

4-10-96

INV. NO.

45175

RECEIVED
ASAC CORP
APR - 1
A-10-96