

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-21675-00-00  
Spot: SWSNENW Sec/Twnshp/Rge: 29-26S-20E  
3979 feet from S Section Line, 2985 feet from E Section Line  
Lease Name: JACK JORDAN Well #: W-19  
County: ALLEN Total Vertical Depth: 876 feet

Operator License No.: 4485  
Op Name: VERDE OIL COMPANY  
Address: 7701 BROADWAY ST., STE 200  
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	870		110 SX
SURF	6.25	25		3 SX

Well Type: EOR UIC Docket No: E19444.21 Date/Time to Plug: 09/20/2016 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: JEFF DALE Company: Phone: (620) 754-3800

Proposed Plugging Method: Run tubing to PBSD. Circulate cement to surface. Pull tubing & fill displacement from surface with cement. Cut off casing strings below plow depth. An estimated 30 sacks of Class A cement will be used to plug well from PBSD to surface.

Plugging Proposal Received By: WitnessType: NONE  
Date/Time Plugging Completed: 09/20/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the the 2.375" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.375" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 20 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
814	832		

RECEIVED  
KCC DIST # 3  
OCT 18 2016  
CHANUTE, KS  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]  
(TECHNICIAN)

KCC WICHITA

OCT 21 2016  
RECEIVED

10-21-16

NOV 02 2016

WJ  
CC-UIC