

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25423-01-00
Spot: SESESE Sec/Twnshp/Rge: 9-18S-25W
396 feet from S Section Line, 405 feet from E Section Line
Lease Name: SUTTON Well #: 1-9H
County: NESS Total Vertical Depth: 4459 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4820		WITH 35 SX CMT
COND 20		90		WITH 10 SX CMT
LI 4.5		8867		4548-8867
PROD 7		4960	1824	WITH 250 SX CMT
SURF 9.625		1575		WITH 605 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2016 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ CURVE WITH 35 SX CMT. PULL CASING. RUN TBG & SPOT 100 SX CMT AT 1620'. PLUG AT 1000' WITH 80 SX CMT. PLUG AT 300' WITH 100 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2016 1:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

10/13/16: SET CIBP @ 4820' WITH 35 SX CMT. 10/14/16: PULLED 1824' OF 7" CASING. RUN TBG TO 1620' & SPOTTED 100 SX CMT. PULLED TBG TO 1000' & SPOTTED 80 SX CMT. NO CIRCULATION. WAITED 1 HOUR. RAN TBG TO 1800' & DIDN'T FIND ANY CMT. PULLED TBG TO 1620' & SPOTTED 100 SX CMT. SDFW. 10/17/16: RAN TBG TO 1357' & FOUND CMT. PULLED TBG TO 1000' & SPOTTED 80 SX CMT. PULLED TBG TO 300' & SPOTTED 100 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
8002	8760		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT* USED COMMON CEMENT BY ORR ENTERPRISE. TMD= 8867'
Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT 18 2016
KCC DODGE CITY

NOV 02 2016
Form CP-2/3