

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-033-21511-00-00
 Spot: SWNENESW Sec/Twnshp/Rge: 5-31S-19W
2228 feet from S Section Line, 3295 feet from E Section Line
 Lease Name: MCKINNEY Well #: 5-1A
 County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 10 SX CMT
COND	13.375	350		350 SX
PROD	5.5	5248	1509	WITH 125 SX CMT
SURF	8.625	714		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/20/2016 8:00 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ 5000'; circulate hole w/mud & cap CIBP with 10 sks cement. Weld on pull sub, pull 5.5" slips, NW BOP w/5.5" rams. Cut & pull free pipi. TIH with tbq & spot the following cement plugs:a) @ 1060' spot with 50 sks Class C Cement;b) @ 730' spot with 50 sks Cement;c) @ 60' to surface spot 20 sks cement.RDMOSU , Cut & cap well and dig up rig anchors.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
 Date/Time Plugging Completed: 10/20/2016 9:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 5000' WITH 10 SX CMT ON TOP. 1ST PLUG AT 1060' WITH 50 SX CMT.
 2ND PLUG AT 730' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5156	5170		
5144	5150		
5137	5140		
5126	5130		
5104	5107		
5095	5100		
5076	5079		
5068	5074		
5050	5170		

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
 OCT 25 2016
 KCC DODGE CITY

Signed _____


 (TECHNICIAN)

11-2-16
 700