

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-20013-00-00
Spot: SWNENW Sec/Twnshp/Rge: 26-22S-2W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: VOGT Well #: 2
County: HARVEY Total Vertical Depth: 3459 feet

Operator License No.: 30280
Op Name: SUNFLOWER WELL SERVICE, INC.
Address: 1770 28TH AVE PO BOX 341
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3459		225 SX
SURF	8.625	277		250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2016 12:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: SUNFLOWER WELL SERVI Company: _____ Phone: (620) 628-4723

Proposed
Plugging
Method:

To plug according to the rules and regulations of the corporation commission

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/29/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:


Sanded back to 2900' capped with 4 sx cement on top. Pressure tested well, perforated casing at 450', circulated 145 sx of cement to surface. Cement fell back inside 4.5" topped with 20 sx cement.

Remarks: COPELAND CEMENT OUT OF BURRTON PROVIDE CEMENT 60/40/4% POZ MIX. TICKET #44811. DENIED
TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

NOV 02 2016

Form CP-2/3

