

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22318-00-00
Spot: SESENE Sec/Twnshp/Rge: 34-29S-4E
4006 feet from S Section Line, 233 feet from E Section Line
Lease Name: MUDDY CREEK SOUTHWEST Well #: 1-A
County: BUTLER Total Vertical Depth: 2925 feet

Operator License No.: 6044
Op Name: STELBAR OIL CORPORATION, INC.
Address: 1625 N WATERFRONT PKWY SUITE 2
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2925		100 SX
SURF	8.625	270		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2016 12:00 AM
Plug Co. License No.: 6044 Plug Co. Name: STELBAR OIL CORPORATION, INC.
Proposal Rcvd. from: ALLEN KEARNS Company: _____ Phone: (316) 264-8378

Proposed Plugging Method: Per KCC instructions.

Plugging Proposal Received By: JERRY SPARLING WitnessType: PARTIAL
Date/Time Plugging Completed: 10/07/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2790', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH W/TBG @ 1850', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 10 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 1775'. RIH ON WIRELINE SET CIBP @ 340'. CUT CASING @ 320', LAYED DOWN 9 JOINTS 5-1/2" CASING (320'). RIH W/ TBG @ 320', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2835	2857		

Remarks: CEMENT TICKET #51506

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

Form CP-2/3

NOV 02 2016
JW