

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-19088-00-01  
Spot: NWSWSWNE Sec/Twnshp/Rge: 30-23S-17E  
3040 feet from S Section Line, 2500 feet from E Section Line  
Lease Name: BRUNER Well #: 2  
County: WOODSON Total Vertical Depth: 550 feet

Operator License No.: 32903  
Op Name: TRIPLE B CRUDE, LLC  
Address: 2100 W VIRGINIA RD  
COLONY, KS 66015

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	920		120 SX
SURF	6	40		10 SX

Well Type: SWD UIC Docket No: D27897.0 Date/Time to Plug: 08/24/2016 12:00 AM  
Plug Co. License No.: 33120 Plug Co. Name: RHODES, DEREK LEON DBA RHODES WELL SERVICE  
Proposal Rcvd. from: MATT BOWEN Company: Phone: (316) 644-8325

Proposed Plugging Method: Well converted to SWD 2001. Plug back to 550' updated ACO-1 submitted 2001. Per KCC Agent Ryan Duling: run 1" pipe to T.D. (550') fill bottom to top with cement.

Plugging Proposal Received By: Witness Type: NONE  
Date/Time Plugging Completed: 08/24/2016 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Ran 1" pipe down the inside of the 2.375" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2.375" casing from TD to surface. Pulled the 1" pipe out of the well and topped the well off with cement. A total of 12 sacks of portland cement was reported used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
440'	450'		

RECEIVED  
KCC DIST #3  
OCT 18 2016  
CHANUTE, KS  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature] E.C.A.S.  
(TECHNICIAN)

KCC WICHITA

OCT 21 2016  
RECEIVED

10-21-16

NOV 02 2016

NO  
CC - UIC