

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-19002-00-02
Spot: NENE Sec/Township/Rge: 4-22S-24W
4683 feet from S Section Line, 517 feet from E Section Line
Lease Name: BINDLEY WF UNIT Well #: 301
County: HODGEMAN Total Vertical Depth: 4703 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4590		WITH 2 SX CMT
DVT		1732		WITH 300 SX CMT
PROD	5.5	4700	0	WITH 175 SX CMT
SURF	8.625	634		WITH 315 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2016 10:00 AM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Revd. from: JOE RUPP Company: NORTH FORK WELL SERVICE LLC Phone: (620) 793-3051

Proposed Plugging Method: SET CIBP @ 4590' WITH 2 SX CMT. RTIH TO 1750' & CIRCULATE CMT TO 0' INSIDE 5 1/2" CASING. CHECK BACKSIDE WITH CMT TO 300#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 09/30/2016 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 4590' WITH 2 SX CMT. PUMP 220 SX CMT WITH 2 SX HULLS AT 1750'. CMT CIRCULATED TO SURFACE THEN FELL BACK. WAITED & TOPPED OFF WITH 70 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4684	4693		
4676	4682		
4670	4674		
4663	4667		
4638	4646		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Kenny Sullivan

(TECHNICIAN)

RECEIVED
OCT 12 2016
KCC DODGE CITY

MS

SA

NOV 02 2016

no

Form CP-2/3