

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-21189-00-00
Spot: SW Sec/Twnshp/Rge: 27-31S-10E
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CLARK Well #: 1
County: ELK Total Vertical Depth: 2116 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2110	1100	
SURF	8.625	125		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/1983 12:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 11/03/1983 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs: _____

Well was plugged before my employment with the KCC. Dumped 10 sacks over perforations at 2012-2018. Ran tubing to 1890' and pumped 15 barrels of mud. Pulled up to 1375' and spotted 10 sack plug. Shot casing off at 1100'. Pulled casing up to 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled casing and topped well off. A total of 170 sacks of cement were used to plug this well.


RECEIVED
KCC DIST #3
OCT 18 2016
CHANUTE, KS
DS

Remarks:

Plugged through: CSG

District: 03

Signed _____



(TECHNICIAN)

KCC WICHITA

OCT 21 2016

RECEIVED

10-21-16

Form CP-2/3

NOV 02 2016

No