

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20930-00-00
Spot: NWNW Sec/Twnshp/Rge: 17-32S-31W
4648 feet from S Section Line, 4626 feet from E Section Line
Lease Name: REISS Well #: 1-17
County: SEWARD Total Vertical Depth: 5835 feet

Operator License No.: 34089
Op Name: AGRICULTURAL ENERGY SERVICES
Address: PO BOX 31865
EDMOND, OK 73003

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4310		WITH 2 SX CMT
CIBP		5475		WITH 2 SX CMT
PROD	4.5	6050	1722	WITH 500 SX CMT
SURF	8.625	1662		WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/14/2016 12:00 PM
Plug Co. License No.: 32721 Plug Co. Name: ELDREDGE WELL SERVICE LLC
Proposal Rcvd. from: MIKE BRADY Company: AGRICULTURAL ENERGY SERVIC Phone: (620) 629-5660

Proposed Plugging Method: CIBP @ 5480' WITH 2 SX CMT. CIBP @ 4310' WITH 2 SX CMT. PLUG AT 1710' WITH 10 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2016 5:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5475' WITH 2 SX CMT. CIBP @ 4310' WITH 2 SX CMT. 1ST PLUG AT 1682' WITH 50 SX CMT. 2ND PLUG AT 562' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5532	5580		
5002	5006		
4993	4997		
4890	4895		
4860	4864		
4635	4640		
4360	4363		



Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
OCT 19 2016
KCC DODGE CITY

Signed

(TECHNICIAN)

NOV 02 2016 Form CP-2/3