

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-093-20752-00-00  
Spot: N2NENE Sec/Twnshp/Rge: 20-25S-36W  
4894 feet from S Section Line, 572 feet from E Section Line  
Lease Name: LEE Well #: 20-1  
County: KEARNY Total Vertical Depth: 5130 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1860		
CIBP		4500		
CIBP		4562		
PROD	4.5	5121	0	WITH 150 SX CMT
SURF	8.625	615		WITH 355 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/13/2016 8:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 4562' WITH 2 SX CMT. TEST CASING TO 700# IF HOLDS PERFORATE AT 1800' WITH 4 SHOTS THEN 50 SX CMT (25 WITHOUT HULLS & 25 WITH HULLS). PERFORATE AT 640' WITH 4 SHOTS & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/13/2016 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4562' & 4500'. RAN CBL FROM 4500' TO 1465'. HAD CMT UP TO 3100' THEN MORE CMT FROM 2050' TO 1700'. LOAD CASING & ATTEMPT TO TEST. WOULD NOT TEST. PUMPING IN AT 1 1/2 BPM AT 150 PSI. ISIP-VACUUM. TAG FLUID LEVEL AT 1700' FROM SURFACE. SET CIBP @ 1860'. LOAD & TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 640'. SPOT 50 SX CMT AT 1840' TO 1000'. CIRCULATE CMT FROM 640' TO SURFACE USING 160 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
4956	4968		

Remarks: \*\*COMLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
OCT 19 2016  
KCC DODGE CITY

Form CP-2/3  
NOV 02 2016