

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23693-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 4-22S-12W  
2265 feet from S Section Line, 2222 feet from E Section Line  
Lease Name: MEYER FARMS Well #: 1  
County: STAFFORD Total Vertical Depth: 3619 feet

Operator License No.: 9090  
Op Name: CHARTER ENERGY, INC.  
Address: PO BOX 252  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3619		
PROD	5.5	3645	1805	WITH 175 SX CMT
SURF	8.625	308		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/26/2016 2:00 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: SAND BOTTOM TO 3320' WITH 5 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 09/30/2016 4:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BOTTOM TO 3320' & TOP IT OFF WITH 5 SX CMT. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3645	3649		
3520	3524		
3464	3470		
3445	3450		
3427	3430		
3370	3374		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed

*Ken Scofield*  
SA

(TECHNICIAN)

RECEIVED  
OCT 10 2016  
KCC DODGE CITY

Form CP-2/3

NOV 02 2016