

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20707-00-00
Spot: NWSE Sec/Twnshp/Rge: 14-20S-8W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HOLLINGER Well #: 1
County: RICE Total Vertical Depth: 1372 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1372		75 SX
SURF	7	207		85 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: STEVE BODINE Company: _____ Phone: (620) 587-5527

Proposed Plugging Method: In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/28/2016 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ck bottom. Perforate at 1050', 650' and 260'. Run tubing to 1320' and pump 50 sxs common cement with 3% CC & 100#s cotton hulls. Pull tubing to 650' and wait 1 hour. Run swab bar down and tag cement at 700'. Pumped 35 sxs with common CC at 650'. Pulled tubing to 260' and circulated cement to surface. Pulled tubing out and topped off.

Perfs:

Top	Bot	Thru	Comments
1136	1156		

Remarks: XCEL WIRELINE PERF TICKET # 1334. COPELAND CEMENT TICKET # 44373. THIS WELL PLUGGED AS PART OF COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

No
NOV 02 2016

1/2