

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22482-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 18-20S-7W
1650 feet from S Section Line, 4620 feet from E Section Line
Lease Name: LIONHEART Well #: 1
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3346		165 SX
SURF	8.625	236		180 SX
T1	2.375	3242		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: STEVE BODINE Company: _____ Phone: (620) 583-5527

Proposed
Plugging
Method:

In accordance with the rules and regulations of the KCC

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 10/27/2016 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, ck bottom. Pump 35 sx's thru tubing at 3340'. Perforated at 1050', 600' and 290'. Run tubing to 1050' and pump 35 sx's with 3% CC, Pull tubing to 600' and wait 1 hr. Run sandline back down and attempt to tag cement--plug had slipped to 1500'. Run tubing back down to 1050' pumped another 35 sx's plug. Let set awhile and tagged at 650'. Pumped 35 sx's at 600', pulled tubing to 290' and circulated to surface. Pulled tubing out and topped off.

Top	Bot	Thru	Comments
3252	3278		

Remarks: XCEL WIRELINE PERF # 1208. COPELAND TICKET # C-44372. WELL PLUGGED AS PART OF COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

No
Form CP-2/3
NOV 02 2016