

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19083-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 17-32S-5E
345 feet from S Section Line, 344 feet from E Section Line
Lease Name: LENA WALKER Well #: 1
County: COWLEY Total Vertical Depth: 3025 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3025		150 SX
SURF	8.625	150		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M, DBA MCPHERSON DRILLING
Proposal Rcvd. from: DON BUTLER Company: _____ Phone: (620) 221-3570

Proposed Plugging Method: As directed by KCC District #2 office

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/10/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

SANDED WELL BACK @ 2955', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. TAGGED PLUG @ 2930'. RIH W/3/4" TBG ON BACKSIDE OF CASING @ 250', MCPHERSON DRILLING ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN 3/4" TBG. RIH W/2" TBG ON INSIDE OF 5-1/2" CASING @250', MCPHERSON DRILLING ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Remarks: COMPLIANCE/ 10 YR RULE CEMEMNT TICKET #36582, & 36586

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

No
NOV 02 2016

✓