

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19084-00-00  
Spot: NESESE Sec/Twnshp/Rge: 17-32S-5E  
990 feet from S Section Line, 330 feet from E Section Line  
Lease Name: LENA WALKER Well #: 2  
County: COWLEY Total Vertical Depth: 3064 feet

Operator License No.: 30169  
Op Name: DOUBLE "D" OIL COMPANY, INC.  
Address: 2009 JEAN CT  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3025		150 SX
SURF	8.625	150		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING  
Proposal Rcvd. from: DON BUTLER Company: \_\_\_\_\_ Phone: (620) 221-3570

Proposed Plugging Method: As directed by KCC District #2 office

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/20/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Sanded well back @ 2955', Dump bailed 4 sxs cement on top of plug. Tagged plug @2930'. RIH w/ 3/4" tbg on backside of casing, McPherson Drilling established circulation, mixed and pumped 90 sxs 60/40 poz mix 4%gel to surface. Cement circulated. Layed down 3/4" tubing. RIH w/ 2" tbg on inside of 5 1/2" casing @ 250', McPherson Drilling established circulation, mixed and pumped 60 sxs 60/40 poz mix 4% gel to surface. Cement circulated. Daniels Ready Mix cement ticket #36650, & #36651.

Perfs:

Top	Bot	Thru	Comments
3025	3064	OH	

Remarks: COMPLIANCE/10 YR RULE

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

Form CP-2/3

NO  
NOV 02 2016