

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-20912-00-00

Spot: SWNESWNE

Sec/Twnshp/Rge: 4-16S-10W

3343 feet from S Section Line, 1919 feet from E Section Line

Lease Name: HEITSCHMIDT

Well #: 12

County: ELLSWORTH

Total Vertical Depth: 3356 feet

Operator License No.: 6901

Op Name: D S & W WELL SERVICING, INC.

Address: 1822 24TH STREET  
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
|--------|------|------------|-------------|----------|

|      |     |      |  |        |
|------|-----|------|--|--------|
| PROD | 5.5 | 3356 |  | 175 SX |
|------|-----|------|--|--------|

|      |       |     |  |        |
|------|-------|-----|--|--------|
| SURF | 8.625 | 562 |  | 350 SX |
|------|-------|-----|--|--------|

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/29/2016 12:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: JIM LYMAN

Company: D S & W WELL SERVICING INC

Phone: (620) 793-5838

Proposed  
Plugging  
Method:

As per KCC orders

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 10/24/2016 2:00 PM

KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

**Perfs:**

MIRU, pull out rods and tubing. Perforate at 1300', 950', and 610'. Run tubing to 3238' and pump 50 sx's cement with 100#'s cotton hulls. Pull tubing to 1300' and pump 35 sx's common cement, 3% CC with 100#'s cotton hulls. Pull tubing to 950'. Let set for 1 hr., run tubing back down and tagged cement at 1140'. Pulled tubing back up to 950' and pumped 35 sx's common cement, 3% CC. Pulled tubing to 610' and circulated cement to surface out of both casings. Pulled tubing out and topped off.

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3289 | 3298 |      |          |
| 3288 | 3298 | CSG  |          |
| 3276 | 3279 | CSG  |          |

Remarks: GRESSELL PERF TICKET #1437. COPELAND TICKET # C-44365.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

Form CP-2/3

NOV 02 2016