

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21248-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 26-32S-25W
5112 feet from S Section Line, 1042 feet from E Section Line
Lease Name: BIG BASIN Well #: 3
County: CLARK Total Vertical Depth: 5800 feet

Operator License No.: 35312
Op Name: PARWEST LAND EXPLORATION, INC.
Address: 2601 NW EXPRESSWAY SUITE 707 WE
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3620		WITH 2 SX CMT
COND	20	40		
	11 8.625	995		WITH 725 SX CMT
	12 13.375	385		WITH 300 SX CMT
PROD	4.5	4000	1008	WITH 210 SX CMT
SURF	7	1200		WITH 300 SX CMT

Well Type: SWD UIC Docket No: D28240.0 Date/Time to Plug: 10/28/2016 9:00 AM
Plug Co. License No.: 35401 Plug Co. Name: ROADRUNNER WELL SERVICE LLC
Proposal Revd. from: RICHARD DONOFRIO Company: PARWEST LAND EXPLORATION Phone: (405) 843-1917

Proposed Plugging Method: SET CIBP @ 3620' WITH 2 SX CMT. RUN TBG TO 1200' & PUMP 15 SX GEL & 50 SX CMT WITH 100# HULLS. PULL TO 410' & CIRCULATE CMT TO SURFACE. TOP OFF AS NEEDED.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2016 11:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

SET CIBP @ 3620' WITH 2 SX CMT. SHOT 4 1/2" CASING OFF AT 1293'. COULD NOT PULL. SHOT OFF AT 1256' COULD NOT PULL. SHOT OFF AT 1008' & PULLED FROM THERE. 1ST 1008' WITH 100# HULLS & 50 SX CMT. 2ND PLUG AT 410' WITH 80 SX CMT TO SURFACE. TOPPED OFF WITH 10 SX CMT.

Top	Bot	Thru	Comments
3670	3790		

Remarks: USED CLASS A CEMENT BY EXEL.

Plugged through: TBG

District: 01

RECEIVED
OCT 31 2016
KCC DODGE CITY

Signed Jerry Anderson
SA (TECHNICIAN)