

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23843-00-00  
Spot: NESWSENW Sec/Twnshp/Rge: 16-24S-13W  
3003 feet from S Section Line, 3405 feet from E Section Line  
Lease Name: RIXON Well #: 1-16  
County: STAFFORD Total Vertical Depth: 4219 feet

Operator License No.: 33936  
Op Name: GRIFFIN, CHARLES N.  
Address: PO BOX 347  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3860		WITH 2 SX CMT
CIBP		4150		
PROD	5.5	4218	1750	WITH 1500 SX CMT
SURF	8.625	303		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2016 8:30 AM  
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.  
Proposal Revd. from: CHARLES N. GRIFFIN Company: CHARLES GRIFFIN Phone: (972) 342-4846

Proposed Plugging Method: CIBP @ 3860' WITH 2 SX CMT. PLUG AT 840' WITH 15 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/13/2016 6:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3860' WITH 2 SX CMT. RTIH. 1ST PLUG AT 844' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 356' WITH 45 SX CMT. RAN OUT OF CMT. TAG PLUG AT 150'. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4169	4171		
4112	4114		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED  
OCT 17 2016  
KCC BOARD CITY

Signed

*Ken Scofield*  
AA

(TECHNICIAN)

*W*

Form CP-2/3

NOV 02 2016