

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-21065-00-00
Spot: NWNWSEW Sec/Twship/Rge: 13-30S-41W
3749 feet from S Section Line, 3794 feet from E Section Line
Lease Name: BARNHARDT Well #: 3
County: STANTON Total Vertical Depth: 5500 feet

Operator License No.: <u>33856</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>WHITE EXPLORATION, INC.</u>	CIBP		5334		WITH 2 SX CMT
Address: <u>1635 N. WATERFRONT PKWY SUITE 1</u>	PROD	5.5	5506	0	WITH 700 SX CMT
<u>WICHITA, KS 67206</u>	SURF	8.625	1652		WITH 620 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2016 2:00 PM
Plug Co. License No.: 31985 Plug Co. Name: GONZALES WELL SERVICE, INC
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: CIBP @ 5334' WITH 2 SX CMT. PLUG AT 1700' WITH 40 SX CMT. PLUG AT 800' WITH 40 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 10/20/2016 4:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

10/19/16: SET CIBP @ 5334' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 40 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. LOST CIRCULATION. PUMPED 6 BBLS GOT CIRCULATION BACK. 3RD PLUG AT 60' WITH 15 SX CMT. PLUG FELL. TOPPED OFF & FELL AGAIN. PUMP 10 SX CMT ON BACKSIDE. 10/20/16: TAGGED TOC @ 1634' AT 9:00 A.M. TAGGED TOC @ 1602' AT 1:40 P.M. 1ST PLUG AT 1569' WITH 40 SX CMT. 2ND PLUG AT 546' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. PUMP 10 SX CMT ON BACKSIDE TO 200 PSI.

Perfs:

Top	Bot	Thru	Comments
5384	5392		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YEARS** USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 25 2016
KCC DODGE CITY

Form CP-2/3

11-02-16
700