

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21023-00-00
Spot: NENE Sec/Twnshp/Rge: 3-32S-33W
4646 feet from S Section Line, 657 feet from E Section Line
Lease Name: HUDKINS Well #: 1-3
County: SEWARD Total Vertical Depth: 5985 feet

Operator License No.: 9953
Op Name: HARRIS OIL & GAS COMPANY
Address: 1620 PENNSYLVANIA ST., #3A
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4880		WITH 2 SX CMT
PROD	4.5	5087	0	WITH 1205 SX CMT
SURF	8.625	1531		WITH 675 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2016 11:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES Phone: (620) 629-3131

Proposed Plugging Method: CIBP @ 4880' WITH 2 SX CMT. TEST CASING. PERFORATE AT 1580' IWHT 50 SX CMT 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 550' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2016 1:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

CIBP @ 4880' WITH 2 SX CMT. PRESSURED CASING TO 300 PSI & HELD. PERFORATE AT 1580' WITH 50 SX CMT 100# HULLS IN THE LAST 25 SX CMT. PERFORATE AT 550' & CIRCULATE CMT TO SURFACE WITH 115 SX CMT. TOPPED OFF WITH 3 SX CMT.

Top	Bot	Thru	Comments
4933	4939		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
OCT 31 2016
KCC DODGE CITY

Form CP-2/3

11-2-16
No