

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20370-00-00  
Spot: NWSEWNNE Sec/Twnshp/Rge: 8-25S-5W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: NORRIS Well #: 1  
County: RENO Total Vertical Depth: 3590 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 3587       |             | 200 SX   |
| SURF   | 8.625 | 213        |             | 200 SX   |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/27/2016 12:00 AM  
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: \_\_\_\_\_ Phone: (316) 215-1873

Proposed  
Plugging  
Method:

Plug to KKC requirements

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/29/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Set CIBP @ 3420' capped with 2 sx cement on top. Perforated casing @ 700' & 325' with 4spf.. Tripped tubing into 700' spotted 40 sx cement with 100 lbs hulls & 3% CC. Waited 2 hours tagged @ 576'. Tripped tubing to 325' circulated to surface with 180 sx cement. Checked top plug 9-29-16, OK


Perfs:

Remarks: COPELAND OUT OF GREAT BEND, TICKET #44331, FIRST 100 SX OF CEMENT WAS CLASS A, THE NEXT 120 SX 60/40 POZ W/4% GEL.

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

*No*  
NOV 02 2016

Form CP-2/3