

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-10000-00-00
Spot: SENE Sec/Twp/Rge: 5-32S-38W
3387 feet from S Section Line, 626 feet from E Section Line
Lease Name: CURTIS A Well #: 2-5
County: STEVENS Total Vertical Depth: 3040 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3039	0	WITH 200 SX CMT
SURF	8.625	611		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/14/2016 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUG AT 1300' WITH 40 SX CMT. PERFORATE AT 630' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2016 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

****TBG STUCK AT 1319.**** 1ST PLUG RTIH TO 1298' & PUMP 40 SX CMT WITH 150# HULLS. TAGGED TOC @ 969'. TEST CASING TO 500#. HOLDING. PERFORATE AT 630' & PUMP 250 SX CMT. CIRCULATING CMT TO 0'.

Top	Bot	Thru	Comments
2854	2940		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Kenny Sullivan
SK

(TECHNICIAN)

RECEIVED
OCT 17 2016
KCC DODGE CITY

NOV 02 2016
700

Form CP-2/3