

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20728-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 15-22S-41W
1270 feet from S Section Line, 1248 feet from E Section Line
Lease Name: HCU Well #: 1521-C
County: HAMILTON Total Vertical Depth: 2907 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2660		
PROD	4.5	2902	0	WITH 550 SX CMT
SURF	8.625	303		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/18/2016 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2016 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2660'. RUN TBG TO 2650' & CIRCULATE CMT TO SURFACE WITH 185 SX CMT. FILL THE ANNULUS WITH 10 SX CMT. TOP OFF 4 1/2" WITH 5 SX CMT.

Top	Bot	Thru	Comments
2716	2732		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)
SA

RECEIVED
OCT 19 2016
KCC DODGE CITY

NOV 02 2016 Form CP-2/3
NO