

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20229-00-00
Spot: NESW Sec/Twnshp/Rge: 9-22S-41W
1986 feet from S Section Line, 3325 feet from E Section Line
Lease Name: HCU Well #: 0921-B
County: HAMILTON Total Vertical Depth: 2808 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2715		
PROD	4.5	2808	0	WITH 550 SX CMT
SURF	8.625	253		WITH 175 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/18/2016 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2715'. RUN TBG TO 2697' & FILL THE 4 1/2" CASING WITH CMT TO SURFACE USING 175 SX CMT. TOP OFF WITH 5 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 400#.

Top	Bot	Thru	Comments
2713	2766		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
OCT 19 2016
KCC DODGE CITY

NOV 02 2016

Form CP-2/3