

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21597-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 34-25S-19W
998 feet from S Section Line, 2296 feet from E Section Line
Lease Name: SMITH TRUST "C" Well #: 1-34
County: EDWARDS Total Vertical Depth: 4754 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 9342 E CENTRAL
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4690		WITH 2 SX CMT
PROD	4.5	4742	1822	WITH 125 SX CMT
SURF	8.625	315		WITH 380 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/04/2016 10:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM Phone: (620) 532-9232

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1360' WITH 12 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2016 3:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

SET CIBP @ 4690' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1330' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Top	Bot	Thru	Comments
4742	4753		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: CSG

District: 01

RECEIVED
OCT 10 2016
KCC DODGE CITY

Signed Ken Scofield
5A (TECHNICIAN)

Form CP-2/3

NOV 02 2016
MD