

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-187-20391-00-01  
Spot: NWSW Sec/Twnshp/Rge: 34-30S-41W  
1982 feet from S Section Line, 4547 feet from E Section Line  
Lease Name: TUCKER H Well #: 2  
County: STANTON Total Vertical Depth: 5550 feet

Operator License No.: 31652  
Op Name: NORSTAR PETROLEUM, INC.  
Address: 88 INVERNESS CIR E, UNIT F104  
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		1280		
PKR		5389		
PROD	4.5	5550	0	WITH 250 SX CMT
SURF	8.625	1554		WITH 700 SX CMT

Well Type: DF UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2016 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Revd. from: DAVE PAULY Company: NORSTAR PETROLEUM Phone: (316) 250-2045

Proposed Plugging Method: TBG FREE AT 1226'. PERFORATE TBG AT 1560'. CUT OFF TBG AT 1225'. RUN IN WITH 2 3/8" X 4 1/2" PACKER TO 1100'. PUMP 100# HULLS & 100 SX CMT. RELEASE PACKER & COME OUT OF HOLE. TAG CMT. IF TOC AT 1200' OR ABOVE PERFORATE AT 600' (4 1/2") & CIRCULATE CMT TO SURFACE. IF NOT, RUN PACKER BACK IN & PUMP 50 SX CMT AT 1100' & REPEAT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2016 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**\*\*4 1/2" IS CEMENTED FROM 1325' TO 1500' & 1620' TO 2730\*\*** TBG IS STUCK AT PACKER AT 1280'. 2 PERFORATED TBG SUBS ABOVE PACKER. CUT TBG AT 1225'. LEFT IN HOLE 4165' OF 2 3/8" TBG WITH CUP TYPE PACKER. PERFORATE 2 HOLES IN 2 3/8" AT 1560'. THE 4 1/2" CASING IS PERFORATED AT 1212'-1250'. RUN TBG & PACKER TO 1081'. LOAD 2 3/8" X 4 1/2" ANNULUS. INJECTION RATE DOWN TBG 1 1/2 BPM AT 250#. GOOD BLOW ON THE 4 1/2" X 8 5/8" ANNULUS. POOH WITH TBG & PACKER. SPOT 100 SX CLASS A WITH 3% CC DOWN CASING THROUGH PERFS IN 4 1/2" CASING AT 1212'. DISPLACE TO 900'. NO CIRCULATION. WAIT 2 HOURS. INJECTION RATE DOWN 4 1/2" CASING 1 1/2 BPM AT 450# DECREASING TO 150#. PUMP 50 CLASS A CEMENT WITH 2% CC & DISPLACE TO 700'. SHUTDOWN ON VACUUM. NO BLOW ON 4 1/2" X 8 5/8" ANNULUS. AFTER 1 1/2 HOURS TAG TOC @ 860'. PRESSURE TEST CMT TO 400#. PERFORATE 4 HOLES AT 605' & CIRCULATE CMT TO SURFACE WITH 250 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5426	5440		
5336	5343		
5101	5116		

Remarks: USED CLASS A COMMON CEMENT BY BASIC CEMENTING.

Plugged through: CSG

District: 01

RECEIVED  
OCT 10 2016  
KCC DODGE CITY

Signed

(TECHNICIAN)

Form CP-2/3

NOV 02 2016  
*NO*