

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-20607-00-00
Spot: NWSESE Sec/Twnshp/Rge: 35-26S-24E
1140 feet from S Section Line, 974 feet from E Section Line
Lease Name: SIMPSON Well #: 4
County: BOURBON Total Vertical Depth: 454 feet

Operator License No.: 5616
Op Name: NOAH, CALVIN (DECEASED)
Address: 329 N BIRCH
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	454		
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2016 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: KITT NOAH Company: _____ Phone: (316) 841-9510

Proposed Plugging Method: Run 1"; cement to surface

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 07/28/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to 500'. Hit solid. Pumped and circulated cement through the 1" pipe inside the 2" casing from 500' to surface. Pulled pipe. Ran 1" pipe down the backside of the 2" casing to 275'. Pumped and circulated cement through the 1" on the backside of the 2" casing from 275' to surface. Pulled the 1" out of the hole and topped the well off with cement. A total of 38 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
431	454		

RECEIVED
KCC DIST # 3
OCT 18 2016
CHANUTE, KS
RD

Remarks:

Plugged through: TBG

District: 03

Signed: [Signature]
(TECHNICIAN)

KCC WICHITA
OCT 21 2016
RECEIVED

10-21-16

NOV 02 2016
RD