

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30792-00-00  
Spot: NWNWNESE Sec/Twnshp/Rge: 6-34S-17E  
2427 feet from S Section Line, 1238 feet from E Section Line  
Lease Name: C SMITH Well #: ALL 1  
County: MONTGOMERY Total Vertical Depth: 1182 feet

Operator License No.: 32776

Op Name: PEAK ENERGY, LLC

Address: 2649 CR 2300  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1118		135 SX
SURF	8.625	23		25 SX
T1	2.375	242		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/10/2016 12:00 AM

Plug Co. License No.: 31696

Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: PEAK ENERGY

Company:

Phone: (620) 289-4603

Proposed Plugging Method: Run 2" pipe to td, gel hole, spot 50' plug, pull up to 500', spot 50' plug, pull up to 225', cement to surface, pull pipe out, top off cement, cut well head off 4' below ground level.

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/10/2016 12:00 AM

KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Ran 2" to 1180', gelled hole, spotted 8 sacks cement; pulled up to 500', spotted 5 sacks, pulled up to 225', cemented to surface, pulled pipe out, topped off cement. 30 sacks of portland used

Top	Bot	Thru	Comments
1118	1180		

RECEIVED  
KCC DIST # 3  
OCT 12 2016  
CHANUTE, KS  
RH

Remarks:

Plugged through: TBG

District: 03

Received  
KANSAS CORPORATION COMMISSION

Signed Russell Hine  
(TECHNICIAN)

OCT 17 2016

CONSERVATION DIVISION  
WICHITA, KS

10-17-16

NOV 02 2016

no

Form CP-2/3