

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21184-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 30-19S-31W
947 feet from N Section Line, 335 feet from W Section Line
Lease Name: YAGER Well #: 1
County: SCOTT Total Vertical Depth: 4956 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/17/2016 4:15 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: J.D. Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1490' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CM.T 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 10/17/2016 6:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1490' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

Signed

Michael Maier
JA

(TECHNICIAN)

RECEIVED
OCT 17 2016
KCC DODGE CITY

Form CP-2/3

NOV 02 2016
No