

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-20247-00-00  
Spot: NESENE Sec/Twnshp/Rge: 23-32S-10E  
3637 feet from S Section Line, 346 feet from E Section Line  
Lease Name: SHAFFER E Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 2025 feet

Operator License No.: 30252  
Op Name: PATTESON OIL, A GENERAL PARTNER  
Address: PO BOX 177  
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2025		90 SX
SURF	8.625	40		10 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: DUANE SIMS Company: \_\_\_\_\_ Phone: (620) 725-5695

Proposed Plugging Method: Run 1" to bottom - Cement 5 sacks Run 1" to middle - Cement 5 sacks Run 1" to 550' - Cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 08/18/2016 10:00 AM KCC Agent: DUANE SIMS

**Actual Plugging Report:**

Ran 1" to 1500' and hit bridge. Gelled hole and spotted 5 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 145 sacks of cement were used to plug this well.

**Perfs:**

Top	Bot	Thru	Comments
1983	1985		
1958	1974		

RECEIVED  
KCC DIST # 3  
OCT 18 2016  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT OUT BY THE KCC

Plugged through: TBG

District: 03

Signed *D. A. Lewis*  
(TECHNICIAN)

KCC WICHITA

OCT 21 2016

RECEIVED

10-21-16

NOV 02 2016

ML