

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-23955-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 14-32S-10E
1656 feet from S Section Line, 4968 feet from E Section Line
Lease Name: HUGENOT Well #: 8
County: CHAUTAUQUA Total Vertical Depth: 2060 feet

Operator License No.: 30252
Op Name: PATTESON OIL, A GENERAL PARTNER
Address: PO BOX 177
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2050		50 SX
SURF	7	329		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: DUANE SIMS Company: _____ Phone: (620) 725-5695

Proposed Plugging Method: Run 1" to bottom - Cement 5 sacks Run 1" to middle - Cement 5 sacks Run 1" to 550' - Cement to surface

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/11/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1980' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" to 1000' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
OCT 18 2016
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA
OCT 21 2016
RECEIVED

10-21-16

NOV 02 2016 Form CP-2/3
no