

15-155-01834-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

Drilling
API NUMBER Completed 5-17-42

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Estey "A"

WELL NUMBER #3 SWD

SPOT LOCATION 330'N - 330'E

LEASE OPERATOR Cities Service Oil & Gas Corporation

SEC. 14 TWP. 23 RGE. 10 (E) (W)

ADDRESS 800 Sutton Place, Wichita, Ks. 67202

COUNTY Reno

PHONE # (316) 265-5624 OPERATORS LICENSE NO. 5447

DATE WELL COMPLETED 5-17-42

CHARACTER OF WELL SWD
(OIL, GAS, D&A, SWD INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 4-23-84

PLUGGING COMPLETED 4-26-84

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District #2

Is ACO-1 FILED? Well Completed 5-17-42 IF NOT, IS WELL LOG ATTACHED? Yes

PRODUCING FORMATION Arbuckle DEPTH TO TOP 4400' BOTTOM 4495' T.D. 4495'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232'	- 0 -
				5 1/2"	4000'	- 0 -

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pulled 125 joints 2 1/2" steel tubing, 1 - 5 1/2" packer and 10 joints 2 1/2" FG tubing. Ran 125 joints 2 1/2" tubing open-end to 3815'.

Cement O.H. Arbuckle down tubing w/18 Bbls. gel water, 5 sacks hulls, followed w/100 sacks 60/40 Pozmix plus 3% CaCl-2. Pulled tubing out of cement. Ran temp. survey - top cement @ 500', tag cement in pipe @ 676'. Perforated 5 1/2 @ 450', mix and pump down 5 1/2" w/250 sacks sacks 60/40 pozmix. Circ. cement to surface. Shut in, P & A Complete 1 P.M., 4/26/84.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

Don Thompson - state witness on location.

NAME OF PLUGGING CONTRACTOR Halliburton Services LICENSE No. _____
ADDRESS Box 579, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles N. Richmond (EMPLOYEE OF OPERATOR) ~~XXX~~
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Charles N. Richmond
Charles N. Richmond
(ADDRESS) 800 Sutton Place, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO BEFORE ME THIS 1 DAY OF May, 1984

JACQUELINE PIERCE
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-27-85

Jacqueline Pierce
NOTARY PUBLIC
Jacqueline Pierce

MY COMMISSION EXPIRES: 2-27-85

RECEIVED
STATE CORPORATION COMMISSION
FORM CP-4
REVISED 06-83

MAY 10 1984

CONSERVATION DIVISION
Wichita, Kansas

15-155-01834-00-01
DEEPENING FOR SALT WATER DISPOSAL

Commenced: March 15, 1945

Completed: April 14, 1945

Contractor: Crown Drilling Company

Total Depth: 4495' (Old Total Depth 4000')

Input Test: 110 bbls. water per hour.

CASING RECORD: 8-5/8" @ 232' cem. 150 sacks
5-1/2" @ 4000' cem. 200 sacks

Top Arbuckle 3987'
Penetration 508'
Total Depth 4495'

Ran tubing and set packer at 3995.

RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1984

CONSERVATION DIVISION
Wichita, Kansas

DEEPENING FOR SALT WATER DISPOSAL

Commenced: March 15, 1945

Completed: April 14, 1945

Contractor: Crown Drilling Company

Total Depth: 4495' (Old Total Depth 4000')

Input Test: 110 bbls. water per hour.

CASING RECORD: 8-5/8" @ 232' cem. 150 sacks —
5-1/2" @ 4000' cem. 200 sacks

Top Ar buckle 3987'

Penetration 508'

Total Depth 4495'

Ran tubing and set packer at 3995.

RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1984

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

MAY 10 1984

CONSERVATION DIVISION
Wichita, Kansas