

15-155-01977-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Delivery Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Strike out upper line
when reporting plugging
of formations.

Reno County. Sec. 13 Twp. 23 Rge. 10W (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines CNL NW NW

Lease Owner Pickrell Drilling Co. Inc. et al

Lease Name Blasdel Well No. 1

Office Address 705 4th Natl. Bank Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2/19 19 49

Application for plugging filed 2/20 19 49

Application for plugging approved 2/24 19 49

Plugging commenced 3/12 19 49

Plugging completed 3/18 19 49

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH

4			

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Viola Depth to top 3756 Bottom Total Depth of Well 3773 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	221'	None
				5 1/2	3760'	3256'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 6 sax cement @ 3760', shot casing off @ 3233' - start pipe. Pumped hole full of heavy mud, pull casing. Set rock bridge @ 220', dumped 15 sax cement. Filled hole w/ heavy mud to within 15' of top. Run 10 sax cement for cap on well.

4-6-49

RECEIVED

Conservation Div.

APR - 6 1949

STATE CORPORATION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Pickrell Drilling Co. Inc.

Address 705 4th Natl. Bank Bldg., Wichita, Ks. KANSAS

STATE OF Kansas COUNTY OF Sedgwick ss.

C. W. Sebitts (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

same as above (Address)

SUBSCRIBED AND SWORN to before me this 29th day of March, 1949

My commission expires Jan 28, 1953

22-2026 2-48-15M

Notary Public.

PLUGGING

FILE SEC 13 T 23 R 10W

BOOK PAGE 84 LINE 18

15-155-01977-0000

BLASDEL #1

Location: CNL NW NW 13-23S-10W
Reno County, Kansas.

Commenced: 2/1/49
Completed: 2/13/49
Production: D & A

Operator: Pickrell Drlg. Co., Ralph J. Weaver Jr. et al
Wichita, Ks.

Contractor: Pickrell Drilling Co. Inc.
Wichita, Ks.

Casing Record: 7 jts. 221' of New 8 5/8" 32# Smls Casing cemented
with 135 sax.
119 jts. 3760' of New 5 1/2" 14# Smls. Casing cemented
with 90 sax.

Geological Data: Surf. Elevation 1759'
Top Viola Lime 3756' minus 1997

L O G
(Figures indicate bottom of formation)

Surf. Sand & Clay	45
Sand	100
Red Rock	222
Red Rock & Shale	635
Shale, Shells, Salt	1150
Shale	1330
Lime	1440
Lime & Shale	1635
Lime & Sand	1775
Lime & Shale	2265
Shale	2430
Lime & Shale	2565
Brkn. Lime	2655
Lime & Shale	2755
Lime	3055
Shale & Shells	3150
Shale & Lime	3260
Lime	3335
Shale & Lime	3390
Lime	3565
Chert, Lime & Shale	3625
Chert	3630
Lime	3760 Rotary TD

Cable Tool Log:
White Lime 3760 to 3773 Swab 1/2 B0 and 7 BWFH

The Undersigned, Pickrell Drilling Co., Inc., hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

RECEIVED
 PICKRELL DRILLING COMPANY, INC.
 FEB 16 1949 By Ed Schits
 Secretary

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Be it remembered that on this 7th day of March, 1949, before me the undersigned, a notary public, duly commissioned in and for the County and State aforesaid, came C.W. Sebitts, Secretary of Pickrell Drilling Co., Inc., a Corporation of the State of Kansas, personally known to me to be such officer and to be the person who executed as such officer the foregoing instrument of writing in behalf of said Corporation, and he duly acknowledged the execution of the same for himself and for said Corporation.

In Witness Whereof, I have hereunto set my hand and seal on the day and year last above written.

PLUGGING
 FILE SEC 13 T 33 R 10W
 BOOK PAGE 84 LINE 18

Ethel Zimmerman
Notary Public

My Commission Expires January 28, 1953.