

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 13 Twp. 23S Rge. (E) 10 (W)

Location as "NE/CNW%SW%" or footage from lines C SE SE

Lease Owner Earl F. Wakefield

Lease Name Moeckel Well No. 1

Office Address 515 Union Center Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 13 19 62

Application for plugging filed August 13 19 62

Application for plugging approved August 13 19 62

Plugging commenced August 13 19 62


Plugging completed August 13 19 62

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

One plug 180 feet and twenty sacks cement through drill pipe, 1/3 sack
x hulls and plug 35 feet and 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1962

CONSERVATION DIVISION
Wichita, Kansas

8-27-62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ~~XXXXXXXXXXXX~~ Herman E. Justus
Address Post Office Box 71, Nickerson, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Earl F. Wakefield (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 62

Shanda M. Riley
Notary Public.

My commission expires January 25, 1965



WELL LOG

AUG 27 1962

Earl F. Wakefield
515 Union Center
Wichita, Kansas

MOECKEL #1
SE SE Sec. 13-23S-10W CONSERVATION DIVISION
Reno County, Kansas Wichita, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 8-1-62
Completed: 8-13-62

D & A

Casing Record: 8-5/8" @ 257' w/225 sacks HA-5.

15-155-00406-6000

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	100	1748 Gr.
Sand	100	155	1750 D.F.
Shale	155	257	1753 K.B.
Red Bed	257	490	
Anhydrite	490	520	
Shale & Shells	520	1340	
Shale & Lime	1340	2890	
Lime	2890	2950	
Lime & Shale	2950	3240	
Lime	3240	3616	
Lime & Chert	3616	3641	
Lime & Shale	3641	3789	
Chert & Shale	3789	3810	
Lime	3810	3915	
Simpson	3915	3950	
Lime	3950	3969	
Dolomite	3969	3985	
Total Depth	3985		

<u>FORMATION TOPS</u>	
Anhydrite	490 +1263
Heebner	3055 -1302
Douglas	3078 -1325
Brown Lime	3221 -1468
Lansing	3248 -1495
Conglomerate	3594 -1841
Mississippi	3600 -1847
Kinderhook	3630 -1877
Kinderhook Lime	3765 -2012
Viola	3783 -2030
Simpson	3896 -2143
Simpson Sand	3907 -2154
Arbuckle	3966 -2213
Total Depth	3985 -2232

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SE Sec. 13-23S-10W, Reno County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 15th day of August, 1962.

Carmen Reinhardt Leiker
Carmen Reinhardt Leiker, Notary Public

My commission expires: Jan. 26, 1963.