


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Finney County, Sec. 21 Twp. 22S Rge. (E) 33W(W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner W. L. Hartman
Lease Name Damme Well No. 21
Office Address P. O. Box 54, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 26, 19 76
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 26, 19 76
Plugging completed July 26, 19 76
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Clarence Thomas of Garden City)


Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4875' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	394'	8-5/8"	394'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged Hole w/100 sax @ 2700
50 sax @ 800', 45 sax @ 390',
15 sax 40' to 0, 5 sax in rat hole. Job Completed @ 8:30 P.M.
RECEIVED
JUL 30 1976
CONSERVATION DIVISION
Wichita, Kansas
7-30-76

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allied Cementing Co.
Address Box 31, Russell, Kansas



STATE OF KANSAS, COUNTY OF SEDGWICK ss.
I, M. McCaul, Jr. of Sage Drilling Co. (employee of owner or former or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, contents, and matters herein contained and the log of the above described well as filed and that the same are true and correct.
(Signature)

500 Bitting Building, Wichita, Ks. (Address)
Subscribed and sworn to before me this 27th day of July, 19 76.
My commission expires November 26, 1978.
Louise K. Whitted - Notary Public.

DRILLERS LOG

DAMME NO. 21

CASING RECORD:	OPERATOR: W. L. Hartman	DESCRIPTION:
8-5/8" set @ 394' w/275 sax cement	CONTRACTOR: Sage Drilling Co.	NW NW NE Sec. 21-22S-33W Finney Co., Kansas
TOTAL DEPTH: 4875'	COMMENCED: July 13, 1976	ELEVATION: -2885KB
	COMPLETED: July 26, 1976	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	394	
Sand & Shale	394	1177	
Shale & Red Bed	1177	1480	
Lime & Sand	1480	2055	
Shale & Lime	2055	2364	
Shale & Shells	2364	2530	
Shale	2530	2772	
Lime & Shale	2772	3268	
Shale & Shells	3268	3438	
Lime & Shale	3438	3827	
Lime	3827	3930	
Shale	3930	4044	
Lime & Shale	4044	4325	
Lime	4325	4340	
Lime & Shale	4340	4472	
Lime	4472	4528	
Shale	4528	4582	
Lime	4582	4622	
Shale	4622	4653	
Lime	4653	4706	
Lime & Shale	4706	4805	
Shale	4805	4857	
Lime	4857	4875	D&A

RECEIVED
STATE OF KANSAS
JUL 30 1976
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew



Subscribed and sworn to before me this 27th day of July, 1976.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1978.