


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Finney
Sedgwick County, Sec. 21 Twp. 22 Rge. 33 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner W. L. Hartman
Lease Name Damme Well No. 16
Office Address P. O. Box 54, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal
Date well completed 8-14-56 19
Application for plugging filed 2-11-77 19
Application for plugging approved 2-14-77 19
Plugging commenced 3-1-77 19
Plugging completed 3-1-77 19
Reason for abandonment of well or producing formation _____
No longer needed
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	1325	8-5/8"	1325	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran tubing to 250' - circulated hole clean -
Pumped in 100 sacks common cement
Pulled tubing up to bradenhead
Put away 100 sacks common cement
50# standing pressure. By Allied Cementing Company

RECEIVED
STATE CORPORATION COMMISSION

MAR 08 1977

CONSERVATION DIVISION
Wichita, Kansas

3-8-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor None
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. L. Schmidlapp (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Schmidlapp
P. O. Box 54, Wichita, Kansas 67201
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 77

My commission expires October 30, 1977

Mary D. Loudenback
Mary D. Loudenback Notary Public.



CERTIFIED DRILLER'S LOG

COMPANY: W. L. HARTMAN LEASE: DAMME No. 16
 CONTRACTOR: H & H DRILLING COMPANY LOCATION: SE SW SE
 COMMENCED: 8-8-56 21-22-33W
 COMPLETED: 8-14-56 Finney County, Kansas
 ELEVATION: 2889 R.B. CASING RECORD:
 1325' of 8-5/8", cem. w/850 sacks.
 POTENTIAL:

<u>FORMATION</u>	<u>DEPTH</u>
Surface Clay	0 - 43
Clay & Strips of water gravel	43 - 67
Water gravel with shale in it.	67 - 219
Waxy shale & shells	219 - 318
Shale & Shells	318 - 500
Shale with lime & sand stringers	500 - 600
Sand & Shale	600 - 700
Gypsy Shale & Sand	700 - 820
Lime, Shale & Sand	820 - 971
Red Beds	971 - 1038
Red Beds with Gypsum.	1038 - 1320
Anhydrite	1320 - 1325
RTD	1325

FEB 14 1977
 Notary Public
 Finney County, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

W. L. Hartman
 W. L. HARTMAN

STATE OF KANSAS)
) SS
 COUNTY OF SEBOWICK)

Subscribed and sworn to before me this 24th day of August, 1956.

BERENICE KOOKEN, Notary Public
 My Commission Expires January 12, 1960

Berenice Kooker
 Notary Public