

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-20883-0000

LEASE NAME Cook

WELL NUMBER I-I

1250 Ft. from S Section Line

3914 Ft. from E Section Line

SEC. 15 TWP. 22S RGE. 34 (E) or (W)

COUNTY Rinney

Date Well Completed 3-12-91

Plugging Commenced 12-21-00

Plugging Completed 12-21-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Plains Petroleum Operating Co.

ADDRESS P.O. Box 383

PHONE#(316) 355-7838 OPERATORS LICENSE NO. 04253

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-21-00 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chase Group Depth to Top 2573 Bottom 2635 T.D. 3020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	1728 ft	None
Chase Group	Gas			5 1/2"	3000 ft	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Mix 3 sacks of hulls and 25 sacks of cement to plug Chase Formation perforations from 2573-2373 ft. Pump water spacer to 1800 ft. Mix 200 sacks of cement and plug 5.5" casing from 1800 to 0 ft. Mix and pump 5 sacks down 8 5/8" casing and pressure up to 1000 psi. Cut off casing 3 feet below ground level and weld on steel cap.

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Route 1, Box 49BA; Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Plains Petroleum Operating Company

STATE OF Kansas COUNTY OF Kearny, ss.

Don K. Wilken (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don K. Wilken

(Address) P.O. Box 383; Lakin, KS 67860

SUBSCRIBED AND SWORN TO before me this 11th day of JANUARY, 2001

[Signature] RECEIVED
STATE CORPORATION COMMISSION
Notary Public

My Commission Expires: NOVEMBER 5, 2002

JAN 16 2001

Form CP-4
Revised 05-88

CONSERVATION DIVISION
Wichita, Kansas



1-16-01

[Handwritten initials]